

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of work: Estimate for Improvements to Roads and Drains at Srinivasapura Hemannaswamy Temple Road (Bande Road) in Ward No. 05 Byatarayanapura Sub Division

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	261.53	KSRRB 300 Excavation for road formation KSRRB 300-3. Earth work excavation and foming in embankment by manual means in ordinary soil with initial lead upto 15m, and lift of 1.5m, (when earth ls taken from bank cutting of from borrow pits) including breaking of clods, spreading to required line and level, forming, and cost of all labour complete as per specifications. (excluding watering and compaction of earth) MORTH chapter 3. No. 141/ Item No. 19.3/ PWD SR 2015-16	cum	105.84	
2	101.88	KSRRB 300-1. Earth work excavation by manual means in Hard Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.MORTH chapter 3. No. 141/ Item No. 19.2/ PWD SR 2015-16	Cum	115.56	
3	493.29	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete do- 7.5 cms thick Page No. 28/ Item No. 5.31.1/ PWD SR 2015-16	Sqm	663.12	
4	134.57	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2015-16	Cum	5070.60	
5	7.02	KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 23/ Item No. 5.6/ PWD SR 2015-16	cum	4135.32	

Quantity.	Description	Unit	Rates	
			In Figures	In Words
6 4.86 5.85	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5-1.13 Page No. 23/ Item No. 5.9/ PWD SR 2015-16	Sqm	4905.36	
7 15.30	KSRB 4-6.7 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 16/ Item No. 4.34/ PWD SR 2015-16	Sqm	270.00	
8 2.08	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2015-16	cum	5491.80	
9 13.00	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 109/ Item No. 15.1/ PWD SR 2015-16	Sqm	99.36	
10 20.61	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2015-16	Cum	6198.12	
11 2.30	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46.2/ PWD SR 2015-16	Qtl	64074.14	

Quantity.	Description	Unit	Rates	
			In Figures	In Words
12 217.94	KSRRB M300-53 : Construction of embankment with approved material Gravel/Murum with all lifts and leads, trasnporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications (which includes cost of gravel / murum, watering charges & compaction by vibratory roller) MORTH Specification No. 305. (Page No. 144 & Item No. 19.60) PWD SR 2015--16	Cum	311.04	
13 87.18	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 for raft foundation, column footing, main and secondary beams. Page No. 18/ Item No. 4.48/ PWD SR 2015-16	Cum	6332.04	
14 186.25	KSRRB M2600-3: (ii) Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per drawing & technical specification complete as per specifications, MORTH specification No. 2605, No. 233/ Item No. 31.3 PWD SR 2015-16	M	138.24	
15 871.75	Vaccum De- writing with vaccum pump and suction mat and compaction with skin flater clubbed with floatiog disc including cost of generator, HOM of machinery Sereed Vibratory Power Floaterblade and diisc etc. with all lead and lift No. 171/ Item No. 22.7/ PWD SR 2015-16	Sqm	97.20	
16 363.40	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inclunding loading and unloading. From 0.00 to 2.00 Km (Page No.123,	Cum	73.36	

" DTS Approved
with one correction
at-Item NO: 6."

Chief Engineer
Telahanka Zone
Bruhat Bangalore Mahanagara
Bangalore 92

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92
9/11/16